
The Pre-Design Phase Geomorphic Based Stream Crossing Projects



Michael Love P.E. Arcata, California mlove@h2odesigns.com 707-822-2411



California Department of Fish & Wildlife California Salmonid Stream Habitat Restoration Manual Part XII: Fish Passage Design and Implementation (2009)



Available at:


http://www.dfg.ca.gov/fish/resources/ habitatmanual.asp


Primary Authors:

Michael Love P.E. Michael Love & Associates, Inc.

Kozmo Bates P.E. Olympia, WA














3


















































Estimating Channel Bed Structure Stability		
Table 5.3—A qualitative method for determining channel-bed structure stability. (USFS Stream Simulation Manual)		
Structure composition	Stability Rating	Structure Characteristics
Bedrock	High	Bedrock ledges or falls span entire stream width
Boulder-cobble steps	High	Boulder-cobble steps span entire width of stream. Rocks are tightly keyed in place, and keyed-in material extends below base of scour pool below step.
Cobble-boulder or cobble- gravel pool tail crests or riffle crests	High	Cobble-boulder or cobble-gravel pool tail crests or riffle crests span the entire width of stream. Particles are tightly packed, embedded into the channel bed, and coarser than the remainder of the channel bed.
Log	High	Wood is sound and well anchored, spanning entire stream width.
Composite log and rock	High	Wood is sound and well anchored, may or may not span entire stream width. Rock pieces are well keyed in place and bridge gaps so that composite structure controls width from bank to bank.
Boulder-cobble steps, cobble- gravel steps	Moderate	Steps do not span entire width of stream or are loosely keyed in place. Keyed-in rocks may not extend below base of scour pool below step. Alternatively, step key pieces are not in contact with each other.
Cobble-boulder or cobble- gravel pool tail crests or riffle crests	Moderate	Pool tail crests span entire width of stream, but the largest particles are similar in size to those elsewhere observed along the channel bed. Alternatively, particles are moderately packed and/or moderately embedded into the channel bed.
Log	Moderate	Wood is rotten and punky. It may span entire stream width, but anchoring is susceptible to bank scour and movement during high flood events.
Cobble-gravel steps or pool tail crests	Low	Steps do not span entire width of stream, and/or are composed of loosely packed materials. Pool tail crests are constructed of material no coarser than rest of stream bed.
Log	Low	Wood is very rotten and punky, may or may not span entire stream width, and anchoring is poor and susceptible to bank scour and movement during bankful flood events. Indications of movement are visible where pieces are anchored into the bank.
Composite log and rock, beaver dams	Low	Wood is very rotten and punky, or structure is made of loosely packed pieces that are poorly anchored. Structure does not span entire stream width. Rock is small in size and subject to movement at bankfull flood events. Beaver dams are poorly constructed or old and inactive. Large key logs are not present.







Vertical Adjustment Potential (VAP) Develop VAP with long profile and field investigations: **Channel slopes** \checkmark Stability/mobility of channel type/material Channel controls and anticipated longevity \checkmark [bedrock, large wood, colluvium, hard infrastructure] Knickpoints, evidence of active incision (downcutting) or aggradation Pool scour depths (low VAP) \checkmark Bankfull and floodplain elevations (high VAP) \checkmark Historical information (existing invert elev. and slope) \checkmark 29

